


# R&D Works for Beam Lines at Hadron Hall

K.H. Tanaka for the HD Facility Construction Team



- **Hadron-Hall**: Experimental Hall for  $50\text{GeV}-15\ \mu\text{A}$  Slow Beam
  - The First (Only One?) **KAON FACTORY** in the World
- **Neutrino Beam Facility (JHF- $\nu$ )** : Long Baseline Experiment


# Beam Profile of JHF-50GeV PS (Phase 1-)

- Beam Energy: **50 GeV**  
(30GeV for **Slow Beam**)  
(40GeV for Fast Beam)
- Beam Repetition: **3.4s**
- External Beam Width: **0.7s (1.0s) Slow Beam**
- Beam Intensity:  **$3.3 \times 10^{14}$ ppp, 15 $\mu$ A**  
( $2 \times 10^{14}$ ppp, 9 $\mu$ A)
- Beam Power:  $E_{\text{Linac}} =$  **400MeV (180MeV)**  
**750kW (270kW)**

# Progress in the Last Two Years after NP02 for Hadron-Hall Design

- **NP-Hall Design & Beamlines**  
for the Phase 1 Construction  
– Only One Target / Limited Space
- **Radiation/Heat Resistant Beam Line System** for SY/ $\nu$ -line & NP-Hall
- **T1 Target** & its Related Parts
- **Beam Dump**

# Slow Extraction Beam Line Facility (Phase I)





# Experimental Area Design




Prof. Jun IMAZATO,  
My Previous speaker!

## Primary & Secondary Beam Lines




Prof. Hiroyuki NOUMI,  
**The Next Speaker!**

# Radiation Resistant Beamline System



## Mineral Insulation Cable




Nominal Current (A)	2000	2500	3000	1000*	2000*
Dimensions (mm)					
A: Outward Size	20.0	23.8	28.0	18.0	14.0
B: Insulator Size	18.0	21.6	25.0	16.6	12.6
C: Conductor Size	14.6	18.0	20.0	13.2	9.2
D: Hollow Size	7.4	10.0	10.0	--	--
Cross Section (mm <sup>2</sup> )					
Conductor	150.9	211.7	293.1	168.4	78.8
Insulator	117.7	153.2	227.4	106.6	79.4
Seath	73.4	95.3	150.6	47.8	36.6

\* indicates Solid Conductor MICs. No hollow is in Cu conductor.




# Construction of actual magnet Q440MIC



Fully Inorganic Magnet

# Slow Extraction Beam Line Facility (Phase I)






# Development of remote alignment system for SY and v-beam



Twist Lock




Quick Stand





Twist lock



“Twist Lock” system  
for automated  
magnet lifting



Corner fitting

“Drain trap” type

“Elephant nose” type

Mock up test will be done soon.

Water lock

Ball valves used for steam  
or viscous fluid piping  
on the market

Gasket material : metal,  
graphite, asbestos

KITZ Ball valve









**SY and v line Mockup**

# NP Hall (Phase I)




# NP Facility: Cross-Section




- Sides 9.0m Concrete with 1m Iron
- Upper 6.5m Concrete with 2m Iron
- Lower 7.0m Concrete



# Chimney for NP-Hall Magnets





Water Manifold &  
Electric Connection  
at Service Space

Chimney

Magnet

Chimneyed  
Magnet

# Chimney for NP-Hall Magnets



Magnet **Chimney** Prototype No. 0




# Can be Lifted by Twist Lock



**Ttarget disk**  
5.4cm Thick  
50cm Diam.

# T1 Target R&D (by Yamanoi)



# T1 Target & T1 Downstream


How to solve 200kW Hear Problem?

**Magnets**

**Upstream Collimator**

**Beam Ducts**


**Big Vacuum Chamber insteard of Ducts**





# Residual Dose

30Days Operation/1Day Cooling  
1Year Operation/Half Year Cooling





**T1 Target & T1 Downstream**

**Dr. Hitoshi TAKAHASHI,**




**Beam Monitors**

**Dr. Yoshinori SATO**


**Talk in the Tomorrow Morning!**

# Beam Dump Design

Proton beam  
50GeV-15 $\mu$ A  
(750kW)  
40cm



An Example of the Dump Core  $\frac{1}{4}$  Model Calculation by MARS & ANSYS




OFC  
=8.9[g/cm<sup>3</sup>]  
Thermal  
Conductivity  
390 [W/m/K]

(calculated by Y. SATO & M. MINAKAWA)





# Maintenance/Operation Scenario

- Core Part should be Maintenance Free
- Cooling Water from Service Space(S.S.).
- Reduce the air Pressure in the Taper.
- Beam Stop at High Temp and/or Imbalance Temp. Distribution.



# How to build




Core: **Copper**

High Thermal Conductivity.

**Maintenance**

Service Space Structure.


# Moving of Beam Dump for Extension



Beam dump must be moved for the future extension!






# *How to move it safely?*




- Need to be balanced carefully
- Guarantee flatness of the floor


# How to move

Methods	Advantage	Disadvantage	
Roller	<ul style="list-style-type: none"> <li>◆ Easy</li> <li>◆ Cheap</li> </ul>	<ul style="list-style-type: none"> <li>◆ Manpower &amp; Time</li> <li>◆ Unstable</li> </ul>	
Linear Guide	<ul style="list-style-type: none"> <li>◆ Stable</li> </ul>	<ul style="list-style-type: none"> <li>◆ Expensive</li> </ul>	
Air Bearing	<ul style="list-style-type: none"> <li>◆ Low Friction</li> </ul>	<ul style="list-style-type: none"> <li>◆ Motion Guide</li> <li>◆ Braking</li> <li>◆ Clean Floor</li> </ul>	
Till Tank	<ul style="list-style-type: none"> <li>◆ Space Saving</li> <li>◆ Cheap?</li> </ul>	<ul style="list-style-type: none"> <li>◆ Some Guide for Linear Motion</li> </ul>	
Sliding Shoe	<ul style="list-style-type: none"> <li>◆ Manpower Saving</li> <li>◆ Easy Installation</li> </ul>	<ul style="list-style-type: none"> <li>◆ Organic Material for Shoe</li> </ul>	

# Moving scheme and Radiation



- Residual Radiation after 1 Year Operation/Half Year Cooling at the Core Surfaces
- 500mm Iron will be Left at the Core Surfaces: Less Radiation for Work Places






# Summary & Status

- Facility Design & Beam Line Layout
  - Almost Completed
- High Intensity Beam Handling System
  - Almost Ready.
- Most Serious Parts,  
i.e. Target & Beam Dump
  - Final Stage of Design/R&D.

# Construction Schedule




Magnets etc. at S Y : 2006(H18)

Magnets etc. at NP-Hall : 2007(H19)

The first Beam to NP-Hall : 2008(H20)?

v-Beam : 2009(H21)


# Dates of Remember



- **April 2005:** We can start recycling magnets!
  - **March 2005:** K2K shut down
  - **June 2005:** KEK-PS shut down. The most of construction team should take care of external beam lines of the KEK-PS until then.
- **March 2006:** We can start SY settings & The most magnets should be ready until then!
- **March 2007:** We can start NP-Hall settings
- **Sept. 2008:** The construction should be completed (officially) & The First Beam!

# Magnet Collection Project

## The Latest Contribution!



Test Bending Magnet for J-PARC 50 GeV-PS  
~12Tm, 106mm Gap, 330mm Pole Width



# 18D72 Magnet from FNAL?



# Radioactive Iron from DURATEK



- 1\$/10t in US
- 170\$/1t including transport cost for J-PARC.
- 1/4 of Normal Iron?
- Less than 2nCi/g (10Bq/g)
- Max. 0.3mR at Surface.
- It's NOT Nuclear Wastes.
- Possible in Japanese Law!





Hadron Beam Sub-Group in 2004