


OUTLINE of the K-HALL

K.H. Tanaka for Hadron Beam Subgroup



High Intensity Proton Accelerator Project

Experimental Hall for **50GeV-15 μ A** Slow Beam


The First (Only One?) **KAON FACTORY** in the World

OUTLINE of the K-HALL

- General Layout
- Technical Issues
- Schedule
- Budget

- Secondary Beam Lines & Physics
 - Prof. Noumi
- Target & Beam Dump
 - Dr. Sato

Site View of the Project




Tokai Campus of JAERI

日本原子力研究所 東海研究所




K-HALL is the Facility for:



- High Intensity $50\text{GeV} \cdot 15 \mu\text{A}$ Beam
- Many & Various Experiments
 - 3 Primary Proton Beam Line (A,B,C).
 - 3 Target Stations (T0,T1,T2) in the Line A.
 - T0: Test Beam Lines, Thin (0.5%) Target.
 - T1 & T2: Main Secondary Beam Lines, Thick (30%) Targets.
 - B-Line: For Neutral Kaons and/or Other Special Secondary Line.
 - TX: Target Station for the Immediate Beam Dumping
 - C-Line: For Primary Protons and/or High Momentum beams.
- Future Extension for the Beam Direction

Switchyard and K-Hall (1st Stage)





- One Target station, One Secondary Line.
- 30GeV Operation.
- No Research/Preparation Building.
- Easy Extension to the Beam Direction.


Beam Optics (Slow Extraction)

Outer Line: = 24 mm · mr

Inner Line: = 6 mm · mr



K-HALL (1st Stage)



- Future Extension
 - Second, Third Targets can be placed
- Multi Purpose
 - Neutrals, Primary Beams, High Momentum Beams,
- Stable operation
 - Tight Radiation Shield.
 - Radiation Resistant Beam Line Elements.
 - Facility Design Oriented for the Maintenance.

Beam Profile of JHF-PS(&KEK-PS)

- Beam Energy : 50 GeV (12GeV)
- Beam Repetition: 3.4 s (2.2 ~ 4s)
- External Beam Width : 0.7 s (0.2 ~ 2s)
- Beam Intensity: $3.3 \times 10^{14} \text{ ppp}$
($6 \times 10^{12} \text{ ppp}$: Fast)
($3 \times 10^{12} \text{ ppp}$: Slow)
- Beam Power: 750 kW (6kW, 3kW)

Beam Profile of JHF-PS(1st Stage)

- Beam Energy : 30GeV
- Beam Repetition: 3.4s
- External Beam Width: 0.7s
- Beam Intensity: $>2 \times 10^{14}$ ppp
- Beam Power: >270 kW

Technical Issue

Problem is:

- JHF (50GeV) PS: More than 100 times Higher Beam Power than KEK (12GeV) PS.
 - More than 100 times Higher Radiation Dose.
 - More than 100 times Larger Heat Deposit.

How to Handle MW-Class Beam.

For the Stable Operation

- Tight/Enormous Radiation Shield.
- Radiation/Heat Resistant Beam Line Elements.
- Facility Design Oriented for the Maintenance.

Radiation/Heat Resistant Beam line Elements



- High Radiation Resistance
- High Heat Resistance

Natural Solution: Remove Organic Materials from the Beam Line.

Rubber, Plastic, Oil, Paint, and Semiconductors, etc. etc.


Heat Up of Beam Dump by 750kW Beam

面 (R=1500) からの熱伝達係数を 600W/m²/K とした
熱伝導率を 360w/m/k とした




- Without Water Cooling: Copper melts
- With Water Cooling: Copper Temp. go down to 300

Beam Dump “Housing”



We have to prepare such a tremendous
beam dump with water cooling!

2500A Class Mineral Insulation Cable



MI Cable: Completely Inorganic High Power Cable!

Magnet coil winding by 60m-2500A HC-MIC



High-Pot. leak test



Coil winding!



The first coil of 60m-2500A HC-MIC

Magnet with 60m 2500A HC-MIC Coils



Nominal: 3000A/34V


$T_{\text{water}}=37$ (35Lit./m)

$T_{\text{water}}=60$ (35Lit./m) $T_{\text{coil}}=74$ ($T_{\text{air}}=18$)
@3600A/41V(Max)


Facility Design Oriented for the Maintenance (Maintenance Scenario)

- Remote Maintenance
 - Service Space for Water & Electric power
- Easy Replacement
 - Quick Disconnect from the Service Space


K-HALL DESIGN



K-HALL CROSS SECTION




K-HALL CROSS SECTION





Actual Design: Beam Target Part with Secondary Line.

K-HALL CROSS SECTION



Mockup for K-HALL




Mock up of the K-HALL 1




Status of September 26th 2002

Mock up of the K-HALL 2



Front View





Top View



- Magnet: 8D216MIC
- Outer Size: $1060 \times 850 \times 800 \text{ mm}^3$
- Magnet Gap: $400 \times 100 \times 800 \text{ mm}^3$
- Nominal Current Voltage:
3000 A, 33.1 V
- Weight: ~ 10 ton
- Beam Height: 1200 mm

Alignment


Limiting Plate Type



Pole Guide Type



Pole Guide Trial!



- K-Hall: PG + LP
- SY: LP

Limiting Plate Trial!



Limiting Plates



Pole Guide



Test results

- LP & PG: Within 10 min.
 - PG:
 - We have to see the bottom of the beam line.
 - Pole can be bent by the magnet weight.
 - LP:
 - Wall must be necessary
- Next Step
- Remote TV System.
 - Automated Lifting Tool for Magnet.

Quick Disconnect Devices



Power, signal: Ready

Vacuum: Radial Seal and/or Pillow Seal

Water: Coupler Type or Swage-Lock Type or
Holding-Arm Type

Alignment: Pole Type and/or Limiting Plate Type




Electric Power

Plug-Type Bridge Connector

- Max Cur. 3000A
- Max Volt. 200V
- Limited Space
- 30sec for Disconnection
- Good Results
 - Knife Type
 - Plate Type
 - Plug Type



Full Power Test



➤ Next Step
1600A-class connector for small magnet

Cooling Water Connector

- Regular Pressure: 20 atm.
- Regular Temp. 15-80
- Pure Water
- Size: 2-inches Inner Dia.
- Mineral Seal
- 30s-1min. Disconnect on Hand
- Water Leak: 100ml or less.
- Good Result
 - Holding-Arm Type
- Under Development
 - Coupler Type
 - Swage-Lock Type

Coupler-Type Connector



+ Full Metal Ball Valve for Steam.
KITS, Hisaka, etc.

Vacuum Connector

Inner Dia. 20-30cm

Mineral Seal

Vacuum better than 10^{-6} Torr.

Remote Operation Time:
10-30min.


Good Results (EP1-K6)

- Pillow Seal
- Mechanical Holding Type

Under Development

- Radial Seal

Radial Seal Conceptual View



Interlock Signals

- Full Mineral Thermal Switch
- Water Pressure Switch
- Signal Cables
 - Ceramic Beads Cable
 - Thin MI Cable
- Signal Connectors
 - Full Ceramic FCI Connector
 - Spring Pin Contact Connector

Thermal
Switch



Cables



Ceramic
Beads



Full Ceramic FCI Connector

Thin MIC



How to Introduce Electric Power into the Shield without Ohmic Loss?

- Problem
 - Radiation damage of the Cable insulation
 - Tight Radiation Shielding
 - Ohmic Loss of the Electric Power
- MIC Power Line
- Water Cooled Shield Penetrating Bus Duct



Voltage Drop @ 2000A

4 MICs

- 0.486V, about 7m

10 MFLC Cables

- 0.298V, about 10m

Twice Larger Voltage Drop


Almost No Temp. Rise

Hard Wiring Work


➤ Next Step

Water Cooled Shield Penetrating Bus Duct

Water Cooled Shield Penetrating Bus Duct



Switch Yard




- Difficulty: The Roof is not Open.



Image of the SY


Slope Part of the Neutrino Beam line

Maintenance Scenario at SY



- Long Tools/Handles through the Shield Block.
- Quick Disconnect for Water, Vacuum and Electric Power
- Automatic Alignment by Limiting Plates

Switch Yard Top View



From Upstream;

Right: Manifold + Water Connector

Power & Signal Connector

Left: Limiting Plates

Upper: Crane Lifting Tool

Lower: Pivot Fixture

- Water, Electric Power: Quick Disconnect from the Back of the Shield.
- Vacuum: Radial Seal.
- Magnet Stand: Pivot Fixture
- Alignment: Limiting Plates.
- Automatic Crane Lifting Tool at the Top of the Magnet.




Slope Part of the Neutrino Beam line (Existing)

Image Model
of the SY

Status

- Radiation Resistant Parts/System.
 - Almost Ready.
- Heat Resistant Parts/System.
 - Final Stage.
- Remote Handling System/Maintenance Scenario.
 - Ready/Final Stage

Construction Schedule at Tokai



Magnet Installation in SY is Scheduled in 2004+

Magnet Installation in KH is scheduled in 2006-

Construction Budget

Civil Eng. + Building

- H 1 4 : (1 億¥: Design) 2002
 - H 1 5 : 1 1 億¥ 2003
 - H 1 6 : 1 3 億¥ 2004
 - H 1 7 : 2 7 億¥ 2005
 - H 1 8 : 2006
- Total: 5 1 億¥

Problem:

3億¥ for Neutrino Pre-Construction

Facility (Including Water)

- H 1 4 :
 - H 1 5 :
 - H 1 6 : 6 億¥
 - H 1 7 : 7 億¥
 - H 1 8 : 1 0 億¥
- Total: 2 3 億¥

Problems: Water Pump

1 1 億¥

Radiation Shield


1 0 億¥

1 億¥ = 100M¥ = 1MEuro = 1M\$

Very Much Limited Construction Budget

- Almost NO New Parts for Primary Beams
 - Recycle from the KEK-PS Resources
 - Second Handed Ones
 - Donation
- Zero (or very small) for Experimental Facility
 - BYO
 - HbY
 - Some Delay?

Magnet Transfer Schedule




Problem: Can K2K be Finished in the summer 2004?

Magnet Collection Project




- The budget situation of the JHF is NOT very good.
- Let us construct the JHF as an international Facility/collaboration!
- Let us Collect USED magnets from all through the world!!!!
 - Magnets for secondary lines
 - Dipoles
 - Gap: 15-20cm
 - Width: 30-40 cm
 - Length: ~ 1 m
 - B: ~ 1 m
 - Quadrupoles
 - Bore: 20 – 30 cm
 - Length: ~ 1 m
 - B: ~ 1 Tesla at pole
 - Spectrometers
- Contribution from SLAC, CERN, CEA(Saturne), Tsukuba U, and LANL, BNL.....

Magnet Collection Project from Saturne near Paris



- 2 Spectrometer Systems (SPES-I,II)
- 40 Q-Mags, 30cm 0.8-1.6mL, 1T@pole
- 12 D-Mags, 15-20cm Gap, 1-2mL, 2T

SPES-I is coming to KEK



SPES-I(A23) Magnets

Magnet Collection project from CERN, SLAC, Tsukuba




Antiproton Accumulator Ring from CERN
Fixed Target Facility Magnets from SLAC
Medical Facility Magnets from Tsukuba U.

Radioactive Iron from DURATEC



- 1\$/10t
- 100\$/1t including transport fee.
- 1/10 of Normal Iron
- Max. 2mR at Surface.
- Less than 2nCi/gr (74Bq/gr)
- Nuclear Wastes?
- Scheduling?
- Possible in Japan?

Design Construction of JHF K-Hall



Hadron Beam-Line Subgroup is Responsible