

NuMI Horn Construction and Testing

NuMI Horn Jim Hylen (FNAL) NBI03 November 7-11, 2003 Page 1

At NBI'02

• Just finishing testing of prototype horn

Since NBI'02

Constructed and tested production horns 1 & 2

Will also mention

- Cross Hair Alignment System
- Remote survey rod
- Field Monitoring Bdot Coils
- Remote electrical connection, stripline flex test
- Decay Pipe Magnetic Field Check

ANL has collaborated on horn testing and monitoring




1.87 sec repetition rate

NuMI Horn General Design Features

NuMI Horn Jim Hylen (FNAL) NBI03 November 7-11, 2003 Page 2

Insulation Ring





Production Horn 1 is complete

NuMI Horn Jim Hylen (FNAL) NBI03 November 7-11, 2003 Page 3

Horn remote stripline connection


Horn remote lifting fixture

Stripline flex section

Cone to guide survey pole onto tooling ball

Water drain tank

Lift tables to remotely plug horn up onto module





Production Horn 2 is complete

NuMI Horn Jim Hylen (FNAL) NBI03 November 7-11, 2003 Page 4



Water line
electric break
- rad-hard ceramic
in compression

"Cross Hair"

precision check of

horn position via

beam scan scatter

to ion chamber

Magnetic field mapping Hall probe



Test Pulsing and problems found

NuMI Horn Jim Hylen (FNAL) NBI03 November 7-11, 2003 Page 5

Prototype Horn 1: 10 million pulses (1 "NuMI year") described at NBI'02

- Water drips at quick-disconnects, fixed by making water lines less stiff
- Flaking of nickel at nickel-to-anodize coating transition at inner conductor straight section (for production, nickel coat entire inner conductor, eliminate interface)

Production Horn 1: 0.4 million pulses No problems found

Production Horn 2: 0.4 million pulses No problems found

Remote electrical clamp: 1.8 million pulses No problems found

Flex joint at maximum flex: 0.2 million pulses No problems found

Bdot field monitor upper prototype: 10 million pulses

Temperature fluctuations at connector cause baseline drift – do baseline subtraction

Bdot field monitor lower prototype: 0.2 million pulses


Water collecting at lower feed-through becomes conducting – add drain line




Horn Field Measurement

Main horn field between conductors of NuMI Production Horn 1

NuMI Horn Jim Hylen (FNAL) NBI03 November 7-11, 2003 Page 6





NuMI Horn 1 Measured September 2003

Field between conductors:


 α 1/R symmetrical and matches current better than 1%

Horn Field Measurement

NuMI Horn Jim Hylen (FNAL) NBI03 November 7-11, 2003 Page 7

in 'field-free' region through center of horn

Measurement with probe moving along horn axis




For all three horns

- Prototype Horn 1
- Production Horn 1
- Production Horn 2

fringe field in "field-free" region down center of horn is small (~0.01 Tesla max.)

Have not put this field in Monte Carlo yet; previous studies indicate effect on Far/Near neutrino flux ratio should be small




Decay Pipe as Third Horn? (Shades of Hadron Hose!)

NuMI Horn Jim Hylen (FNAL) NBI03 November 7-11, 2003 Page 8


Just a couple gauss will affect neutrino spectrum if field aligned along whole 675 m of decay pipe

so measured field Oct. 2003






-BY2 BY3 -BY4





Measured Decay Pipe Magnetic Field is Negligible

NuMI Horn Jim Hylen (FNAL) NBI03 November 7-11, 2003 Page 9



Pipe center or Quadrant

Stripline flex test


NuMI Horn Jim Hylen (FNAL) NBI03 November 7-11, 2003 Page 10

Stripline flex region allows horn to move relative to remote clamp for:

- Remote motor controlled horn alignment
- Thermal expansion of stripline from beam and electrical heating

0.2 million horn pulses taken with stripline flexed to maximum specification 3mm horz. + 3mm vert.

No problems found



Remote stripline clamp test

NuMI Horn Jim Hylen (FNAL) NBI03 November 7-11, 2003 Page 11

How to hook and unhook horn from power stripline remotely in radiation area? Shaft toggles clamp to provide pressure for good electrical connection



Contact surfaces fine after two plug/unplug cycles 1.8 million pulses total






Cross Hair Horn Alignment System

NuMI Horn Jim Hylen (FNAL) NBI03 November 7-11, 2003 Page 12

Hole in shield to insert beam loss monitor



12 mm x 1 mm
Aluminum cross hairs mounted on horn

(36 mm x 1 mm for horn 2 upstream)

Function: Check position of horn w.r.t. beam by beam scan (target-out)

Scan: (1) horn 1 neck

(2) horn 1 downstream

(3) horn 2 upstream

(4) horn 2 downstream

Beam loss monitor ion chamber




Figure 9. Schematic of Tevatron loss monitor. The monitor is filled with argon gas at 725 mm of Hg. The guard electrode reduces the leakage curren

NUMI




Horn survey rod

for cross check

Tests give ~ 0.01" transverse accuracy

NuMI Horn Jim Hylen (FNAL) NBI03 November 7-11, 2003 Page 13







Bdot Coil Horn Magnetic Field Monitor

NuMI Horn Jim Hylen (FNAL) NBI03 November 7-11, 2003 Page 14

Three bdot coil units per horn to monitor magnetic field each pulse


First prototype: 8 turns of 0.01 inch diameter 304 stainless steel wire wrapped on MACOR form, 1.010 x 0.363 sq inch per turn mounted to Aluminum Oxide ceramic feedthrough

Problems:

MACOR was borderline for required radiation-hardness, but holes for coil were easy to produce

Significant thermo-electric effects found at wire to pin solder joints, caused readout drift

Puddling water at lower probe feed-through became conductive, affecting readout





Bdot field monitoring coil solutions

NuMI Horn Jim Hylen (FNAL) NBI03 November 7-11, 2003 Page 15

Yt Partially Stabilized Zirconia: high impact resistance rad-hard insulator

Manufacturer managed to produce 0.03" diameter holes for coil wire





Water drain being added to lower feed-through - pipe to water drain tank

DC-baseline subtraction done each pulse to compensate thermo-electric effect

When tested, three coils on horn agreed on field to 1%



Summary and outlook

NuMI Horn Jim Hylen (FNAL) NBI03 November 7-11, 2003 Page 16

NuMI Horns constructed and pulse tested – look good!

Next steps:

- Practice remote mounting of horns to modules (December/January 2003)
- Install in target hall (May/June 2004)
- Practice remote handling in target hall
- Commission with beam (December 2004)