

6-July-2007,
3rd J-PARC PAC

SKS Status Report

Tomofumi Nagae,
Spokesperson of E05


Outline

- SKS Magnet & Ref. System
- New Dipole Magnet
- Beamline MWPC & Readout system
- SKS Detectors
 - SKS, SKS+, SKS- Configurations
- Collaboration

SKS Magnet


Modification of Cooling System

Before reconstruction



Not to be
used

After reconstruction




- 300W He refrigerator
 - Cold Box
 - (Medium) Compressor
 - He Transfer line
 - LN₂ storages
 - etc...
- Cu current leads

Head load
(operation)
~ 5W

- 3.5W GM-JT cryo-cooler x 3
 - shield cooler
- HTC current leads
with GM cryo-cooler

can maintain liquid state of He


Measurement of cooling power of GM-JT cryo-cooler (FY2006)




- Cooling power of GM-JT
 - vs shield temp
 - w or w/o anti-convection device

Results


w/o anti-convection device



w/ anti-convection device



Summary



Cooling power depends on the shield temp.

- 3.1W(71K) → 3.6W(41K)
- add a shield cryo-cooler

Anti-convection is effective.

- at high shield temp.

Cooling power > 3.32W

- Three GM-JT cryo-coolers

SKS magnet reconstruction plan 1



- Modification of cooling system and transportation to J-PARC (FY2007-2008)
 - 8/24 Bidding, 12/25(2008) Finish 168M Yen
 - Modification of cooling system and coil vessels
 - de-assemble of the yoke
 - re-assemble of the yoke and coil etc.
 - cooling test at the factory
- Fabrication of GM-JT cryo-coolers (FY2007-2008)
 - In preparation of doc. 4/25(2008)
 - 2 cyro-coolers and 1 compressor, etc.. 30M Yen

SKS magnet reconstruction plan 2

- FY2007
 - disconnection of power and monitor line, etc.
 - purchase of supplying goods (shield cooler,,)
- FY2008
 - connection of power, signal and gas lines
 - construction of interlock and monitor system
 - cooling and excitation test at J-PARC site
(2008 Feb. – Mar.)

New Dipole Magnet

Dipole magnet for SKS+



- Reused magnet yoke
- 20cm gap
- ~1.5 Tesla
- Window frame type

Additional dipole magnet may affect SKS coils and their support.



Estimation of electromagnetic force by “ANSYS” code

Results (w/o end-gaurd)


		SksDMag200A7 (1/2 Model)		SksDMag200A8 (1/4 Model)		TOSCA (Toshiba)	
		Fx [ton]	Fy [ton]	Fx [ton]	Fy [ton]	Fx [ton]	Fy [ton]
Only SKS	Coil	1.46	12.11	0.00	22.82	0.54	18.75
	Yoke	1.67	-18.32	0.00	-19.57	0.39	-25.74
	Total	3.13	-6.21	0.00	3.26	0.92	-6.99
No Excitation	Coil	1.43	12.00	0.50	22.72	-1.26	1772
	Yoke	1.88	-18.30	0.02	-19.55	1.11	-30.12
	Total	3.31	-6.30	0.52	3.17	-0.15	-12.40
	dC	-0.03	-0.11	0.50	-0.10	-1.80	-1.03
	dY	0.21	0.02	0.02	0.01	0.72	-4.38
	dT	0.18	-0.09	0.52	-0.09	-1.08	-5.41
Excitation	Coil	0.33	12.87	-2.12	23.60	-2.56	18.46
	Yoke	1.38	-18.31	0.22	-19.57	0.82	-30.06
	Total	-1.42	0.77	-1.90	0.77	-1.74	-11.60
	dC	-1.13	0.76	-2.12	0.78	-3.10	-0.29
	dY	-0.29	0.01	0.22	-0.01	0.43	-4.32
	dT	-1.42	0.77	-1.90	0.77	-2.66	-4.61

Results (w/ end-guard)

		w/o EG		w/ EG(4cm)	
		Fx [ton]	Fy [ton]	Fx [ton]	Fy [ton]
Only SKS	Coil	-5.96	41.52		
	Yoke	0.85	-21.38		
	Total	-5.11	20.14		
No Excitation	Coil	-5.97	41.39	-5.87	41.28
	Yoke	1.07	-21.36	1.29	-21.38
	Total	-4.90	20.03	-4.58	19.90
	dC	-0.01	-0.13	0.09	-0.24
	dY	0.22	0.02	0.44	0.00
	dT	0.21	-0.11	0.53	-0.24
Excitation	Coil	-7.07	42.30	-6.43	41.88
	Yoke	0.56	-21.35	0.84	-21.40
	Total	-6.51	20.95	-5.59	20.48
	dC	-1.11	0.78	-0.47	0.36
	dY	-0.29	0.03	-0.01	-0.02
	dT	-1.40	0.81	-0.48	0.34

End guard can reduce the force to $\sim 1/2$.

Present Design



Gap 20cm
96 turns/Coil
1.5 T @ 2000A


Power Supply
2000A-135V
(320kW)

Cooling water 7/Coil
230 L/min. @ 1.0MPa


will be fabricated in 2007FY by Grand-In-Aid

Beamline MWPC

1mm MWPC



32ch. half-pitch readout connector




- 15 $\mu\text{m}\phi$ anode wire
- 1mm A-A spacing
- 3mm A-Cathode gap

- 256 ch./plane
- X-U-V (half-size)
- $\pm 15^\circ$ for U and V


Efficiency measurements with $^{90}\text{Sr}/\text{Y}$ source

Ar(80):iso-C₄H₁₀(20) gas

ASD board with SONY-ASD(80ns)





SONY-ASD(16ns)





Geometry coverage
only 16 channels sum

Discharge Problem

- Discharge occurs at the edge region around the plateau region $\sim 3.0\text{-}3.5$ kV.
- Once discharge occurs, the surface of cathode conductor is damaged.



Discharge at the edge region




- Case.1
All 15μmφ

Very high field at the edge region

- Case.2
30μmφ for #1 and 2

However discharge occurred !!


Improved configuration to avoid discharge & cathode damages




G10 frame

- The edge wire is covered by G10.
- Wire dia. $15\mu\text{m} \rightarrow 12.5\mu\text{m}$
- Cathode material
 - Aramid($6\mu\text{m}$)+Al (Present)
 - PET($12\mu\text{m}$)+Al
 - PET+Carbon ?


MWPC Readout



Readout System



ASD board



- 32ch./board
- SONY ASD chip with 80ns
- LVDS output
- +3.3V, -3.0V


20 boards were fabricated for test.

1. We have enough number of 80ns chip
2. We will obtain 16ns chips (1.8K, 4.8Kch.) this year
3. Another ASD chips are under development by 測定器開発室


4ch./board
gain programmable
half-swing pECL output
+5V

MWPC Encoder

- 32ch. / card
- 4 cards / COPPER board
- acceptable signal
 - LVDS
 - ECL
 - pECL




Traditional MWPC encoder scheme




New MWPC Encoder Scheme




New MWPC Encoder Sceme



New MWPC Encoder Scheme




New MWPC Encoder Scheme



MWPC Readout Status


- Basic operation and performance were checked for encoder card.
- Beam test will be done July 10, 2007.
- Minor bug of the firmware was found.
- COPPER boards, FINNESE encoder cards, trigger board, and crates were already fabricated.
- CPU or SiTCP is needed. (not COPPER-Lite)

New MWPC Encoder Scheme



SKS Detectors


Three Modes of SKS



- Present configuration
- 100° bending angle
- ~900 MeV/c max. momentum at 2.7T
- 100 msr solid angle
- best resolution was achieved at 2.2T


E19, E10-1

E10-2, E18



- New dipole magnet
- 95° bending angle
- 1.1 – 1.5 GeV/c
- ~30msr

E05



- No focusing property
- ~130msr@ 1.4 GeV/c

E13

Upstream Chambers

	SKS	SKS+	SKS-
1 st Chamber	250 ^H x120 ^V mm ²	250 ^H x120 ^V mm ²	~400 ^H x200 ^V mm ²
# of layers	4 or 6	4 or 6	4 or 6
High rate	Yes(Ultra)	Yes	Yes
2 nd Chamber	400 ^H x200 ^V mm ²	400 ^H x200 ^V mm ²	~550 ^H x200 ^V mm ²
# of layers	6	6	4
High rate	Yes	Yes	Yes(Medium)
3 rd Chamber		1100 ^H x300 ^V mm ²	
# of layers		3 or 4	
High rate		No	

E03 (E07) requires a 400x250 mm² high-rate chamber

Upstream Chambers

	SKS	SKS+	SKS-
1 st Chamber	250 ^H x120 ^V mm ²	250 ^H x120 ^V mm ²	~400 ^H x200 ^V mm ²
# of layers	4 or 6 3mm DC 1mm PC	4 or 6	4 or 6
High rate	Yes(Ultra)	Yes 3mm DC(BC)	Yes 3mm DC
2 nd Chamber	400 ^H x200 ^V mm ²	400 ^H x200 ^V mm ²	~550 ^H x200 ^V mm ²
# of layers	6	6	4
High rate	Yes 3mm DC	Yes 3mm DC	Yes(Medium)
3 rd Chamber		1100 ^H x300 ^V mm ²	existing
# of layers		3 or 4	5mm DC
High rate		No	

E03 (E07) requires a 400x250 mm² high-rate chamber ??

Downstream Detectors

SKS

- Tracker
1x1 m² x 2
- TOF Wall
1.05x1 m²
- AC x 2
1.2 x 1 m²
- LC Wall
1.4 x 1.2 m²

The present setup.

SKS+

- Tracker
- TOF Wall 1
- AC x 2
- TOF Wall 2
- Water Cherenkov


SKS-

- Tracker
2 x 1 m² x 2
- muon filter
- scintillator wall 1
- iron block
- scintillator wall 2

BD from BNL

BT from BNL

SKS+ Configuration with BDs



Collaboration

Meetings

- 1st International collaboration meeting
 - Oct., 2006 at HYP06
- Collaboration meeting among various SKS experiments
 - May 10, 2007 at KEK
- 2nd International collaboration meeting
 - June 2, 2007 at NP@J-PARC in Tokai
- E05 Italy group meeting
 - June 24, 2007 in Varenna

Job Assignments (1)

- 1mm MWPC R&D and fabrication
 - KEK, Dubna
- MWPC readout – ASD and encoder –
 - KEK with help of electronics system group
- 3mm DC R&D and fabrication
 - Kyoto, KEK
- BH1
 - KEK, already fabricated
- BH2
 - KEK

Job Assignments (2)

- BD, BT modification and maintenance
 - Tohoku, Freiburg, MSU
- AC
 - T.B.A. (KEK? Osaka?)
- DAQ
 - KEK, RIKEN(E15) with help of electronics system group
- Water Cherenkov (E05)
 - Italy
- Dipole magnet, DC3 (E05)
 - KEK
- Muon filter, etc (E13)
 - Tohoku

Requests to KEK

- Support for Travel expenses to send people to J-PARC
- Budget allocation for Facility-oriented supports:
 - Trailer houses, Stock room service, Electronics pool, etc.
- Support for Experiment Preparation Area

Beam Request

- We will be ready for the first beam by April, 2009.
- We need test beams for detector checks from Jan. to March, 2009.
- We want to start the first physics data taking not later than September, 2009.