# **Status of the T2K Detectors**

### J-PARC PAC KEK January 8, 2008



Dave Wark Imperial/RAL

Imperial College

London



### Super Kamiokande Rebuilt

### Super-K III

### New electronics and DAQ system for the SK detector



#### Preparation of the new system is on schedule!



## 280m Near Detectors



# Progress on 280m Hall

## **INGRID On-Axis Detector**

### Japan/France/UK effort Must be operating April 1, Dave Wark 2009 for first beam.

**J-PARC PAC Jan. '08** 

The tracking p

Distribute competrips to compens

# MPPC (aka SiPMs) Status

280m detectors require readout of ~10<sup>5</sup> fibers in a 0.2T magnetic field.



Imperial Collene/RAI

 Conventional photodetectors were unsuitable, so we decided to use SiPMs (or MPPCs) despite lack of commercial availability when adopted.

 Hamamatsu have now produced a version with agreed T2K specifications, will deliver 5k/month starting in early 2008 at 1,900 ¥ (plus 5% tax) when purchased within Japan.

# MPPC Stability Test

- 20 MPPCs (400 pixs, 1.1mm<sup>2</sup>) underwent 31-day heating test at 80°C, U<sub>BIAS</sub>=71.6 V: ALL SURVIVED
- · No visible changes on the surfaces (microscope)
- Gain is stable within 2-3%
- Signal (sensitivity to light) is stable within 4-5% for "heated" MPPCs, but it looks like there is a tendency to decreasing (if to compare with the reference "not heated" MPPCs)
- Cross-talk is stable within 10% (for both "heated" and "not heated" groups), probably better for "heated"

6 December, 2007

M Khabibullin Heating test results of 20 MPPCs at INR

11

Aging test at LSU (3 sensors, 80° for 120 days, no sign of changes in gain or dark rate at few % level

## **INGRID** Schedule



**J-PARC PAC Jan. '08** 

# 280m Off-Axis Detector



# The PØD Design

#### 



Solidworks design assembly

- 3 Super-PØDules
  - ♦ Upstream ECAL (3200 kg)]
    - 🗢 7 PØDules
    - 7 4mm-thick lead radiators
  - ♦ Target (11000 kg))
    - 🛥 2857.3 kg water
    - 🗢 26 PØDules
    - ✤ 25 1.6mm brass radiators
    - ✤ 25 Water target layers
    - Split into 2 sub-units for preinstallation handling
  - Central ECAL (3200 kg)]
    - ≁ 7 PØDules
    - ✤ 7 4mm-thick lead radiators
- Total Mass is 17600 kg



Measurements of light yield exceed specification Dave Wark Imperial College/RAL

**POD Schedule** 

ID	0	WBS	Task Name	% Complete	Q1 Q3	Q1 Oct Jan	Q3 Apr Jul Oct	Q1 Jan Apr	Q3	Q1 Aor	Lange Carlor
1		1	Beam Line	0%		0%					
2		2	US-B280 Near Detector (ND-280)	47%							47%
3		2.1	PI-Zero Detector (P0D)	47%							47%
4		2.1.1	P0D Prototype, Design and Development	82%			1	82%			
5	$\checkmark$	2.1.1.1	Initial PoD Design	100%				100%			
16		2.1.1.2	P0Dule Prototypes	90%	-		1	90%			
114		2.1.1.3	Water Target Prototypes	68%				68%			
131		2.1.1.4	Electronics Mounting and Cooling Prototypes	80%	-			80%			
149		2.1.1.5	Light Injection (Optical Calibration) System Prototypes	78%				78%			
177	$\checkmark$	2.1.1.6	Prototype Photosensor Testing	100%			100%				
191		2.1.1.7	Super-P0Dule Assembly Plan	93%				93%			
198		2.1.1.8	P0D Mounting and Installation	91%				91%			
205		2.1.1.9	P0D Production, QC, and QA Planning	48%				48%			
223		2.1.1.10	Slow Control Electronics	68%	U. U.			68%			
233		2.1.1.11	P0D Utilities in ND-260 Design and Testing	93%			93				
251		2.1.1.12	P0D Front-End Electronics Design and Prototypes	89%				89%			
259		2.1.1.13	Radiator Design and Prototypes	26%				26%			
269		2.1.2	Testing & Pre-Production Reviews	3%				3%			
270		2.1.2.1	Mechanical Design and Production Review	0%				96			
278		2.1.2.2	Prototyping Results	3%				3%			
303		2.1.2.3	Testing & Pre-Production Reviews Complete	0%				<b>€</b> 4/4			
304		2.1.3	Production	15%						15%	
305		2.1.3.1	Project Engineering	45%						45%	
310		2.1.3.2	P0Dule Production	8%					8%	•	
435		2.1.3.3	Water Target Production	0%					0%		
443		2.1.3.4	Electronics Mounting and Cooling	0%					0%		
465		2.1.3.5	Light Injection System	0%				ý v v	)%e		
473		2.1.3.6	Photosensors	7%					7%		
489		2.1.3.7	Super-P0Dule Assembly	0%					0%		
495		2.1.3.8	Super-P0Dule Mounting and Installation Hardware	0%				-	0%		
506		2.1.3.9	P0D Integration and Checkout	0%						V%	
534		2.1.3.10	Slow Control Monitoring and Electronics	0%					0%		
543		2.1.3.11	PoD Utilities	0%			<b></b>		0%		
565		2.1.3.12	Front-End Electronics	0%					0%		
574		2.1.3.13	P0D ECal Radiator	0%					0%		
582		2.1.3.14	Shipping to Japan	0%				-		0%	
586		2.1.3.15	Production Complete	0%				-		-3/24	
587		2.1.4	Instellation	0%							0%
588	112	2.1.4.1	PoD Utility Installation	0%						<b>W</b> 0 %	1
605		2.1.4.2	P0D Detector Installation	0%							10%
617		2.1.4.3	PoD Installation Complete	0%							7/31
618		2.1.5	Pi-Zero Detector (P0D) Complete	0%							7/31



## FGD Progress

### Dark Box/Mechanical Design



ANSYS calculations complete. TRIUMF design review in April 2007. First dark box now under construction.

Imperial College/RAL

# FGD Progress

### XY Module Construction

- Each module consists of an X layer, a Y layer and two G10 skins.
- Considerable R/D was done for module gluing procedure.
- Metal jig was constructed to ensure that X and Y layers were aligned and perpendicular.
- currently 20 of 24 modules glued





# TPC Progress



ALUMINUM OUTER STRUCTURE

ELECTRONICS COVER



## **TPC Progress**



# ECAL Progress



## **ECAL Progress**

- DS ECAL module is now fully specified and designed
- Detailed drawings for components orders are done
- Final Design Review: 12 July @ Daresbury
  - Thanks to C. Hearty, W. Toki, R. Langstaff, D. Warner
- Barrel ECAL modules use same design up to dimensions and fixing points (to the magnet)



# ECAL Progress



## **SMRD** Progress



## SMRD production status

- first batch of ~1000 scintillators has been extruded
- first (relative) light yield measurements indicate good quality (as expected)
- S-groove has been machined for large fraction of first batch of scintillators
- WLS fiber segments have been tested (and QA continues)
- first batch of ~1000 endcaps have been produced
- next step:
- Assembly of modules (scintillator, WLS fiber, endcap, stainless steel enclosure) is ready to start now
- Slippages within contingency, delivery of modules by summer 2008 still on schedule

## **Project Integration and Schedule**



# **Project Integration and Schedule**

-
,
Anarat (genes)
(Contraction (FER) Rect on (Executions)
<u> </u>
<ul> <li>Constrainty State Constraints (SER) Meeting (SER) (SER)</li> </ul>
<b>6</b> 04
(IX)
and a second sec
<b>b</b> 2
· · · · · · · · · · · · · · · · · · ·
4819
Herbary (TMASSER)
Crane/Heavy Cong Contractors (FER 2 March ang (FEAC 4 EE ghore )
construction of construction (see larger of Carter address)
Committeen Cong Contractors (CDF Little org (TRACKER)
contraction of a new rest (reaction of the rest from )
<ul> <li>Compared and property (apply and (processing))</li> </ul>
Sarve Snee (KEX)
Barrey Strap (KEK)
spinor involution (per with press in the press)
Personal Lave and Deck 1
• ***
· · · · · · · · · · · · · · · · · · ·

## **Overall Technical Situation**

- All sub-detectors progressing, some delays here and there:
  - MPPC delivery has slipped a month,
  - TPC boxes taking longer than expected to manufacture
  - Prototype FGD water layers showing some cracking, changing the glue seems to have fixed it, no delay anticipated.
  - Some delays in BE electronics firmware
- Overall the progress is on track for on-time installation with two exceptions
  - Barrel ECAL will not be available for first run.
  - If TPC box production cannot be sped up we may not have the furthest upstream TPC in time for first run.
- Major technical risks are being retired and milestones reached.
- The installation and commissioning schedule for the 280m detectors is aggressive, in particular for the magnet/SMRD, but large amounts of effort are going into planning and no show-stoppers are known.

- Canada
  - Contributions:
    - All the FGD except photosensors
    - TPC mechanical and field cage, integration, gas system
    - Slow Controls and Monitoring
    - Cont. to Beamline: OTR Monitor, Remote handling for hot cell, beam position/profile monitors and vessel
    - nd280m offline software
  - Funding situation: secured with yearly review

- France
  - Contributions:
    - INGRID detector (LLR)
    - TPC Micromegas and FE electronics (Dapnia)
    - TPC BE electronics (LPNHE)
    - Beamline quench detection system
    - Power supply for the UA1 magnet
    - Funding situation: secured.

### • Germany

- Contributions:
  - UA1 Magnet moving system
  - TPC gas monitoring
- Funding situation: request submitted, decision on Jan.
   10

#### Italy

•

- Contributions:
  - UA1 Magnet preparation
  - TPC calibration
- Funding Situation: secured

#### Japan

#### Contributions:

- J-PARC
- Most of SK, and the SK rebuild and upgrades
- Most of the T2K beamline, target, and beam dump including beamline monitors and muon monitor
- Infrastructure for the 280m facility
- INGRID detector
- FGD photosensors
- SMRD FEE
- Cont. to NA61
- Funding situation: secured, with additional funding from MEXT in form of competitive grants.

•

### • Poland

- Contributions:
  - Cont. to SMRD
  - Cont. to NA61
  - nd280m offline software
- Funding situation: secured
- Russia
  - Contributions:
    - Cont. to SMRD
  - Funding situation: secured
- South Korea
  - Contributions:
    - Beamline proton monitor electronics
  - Funding situation: secured

### Spain

- **Contributions:** 
  - TPC testing, calibration, and gas monitoring
  - Cont. to UA1 magnet
  - nd280m offline software
- Funding situation: secured
- Switzerland
  - Contributions:
    - Cont. to TPC mechanics, testing, and assembly
    - Major contributions to
       NA61
    - Major Cont. to UA1 magnet
    - nd280m offline software
    - Funding situation: secured subject to annual review

### United Kingdom

•

- Contributions:
  - BEE for ECAL/P0D /SMRD/INGRID
  - Cont. to beamline beam window, baffle, and engineering for target and dump design, target remote handling
  - Basket/basket stand
  - ECAL (all)
  - FEE design for P0D/SMRD/INGRID
  - DAQ for 280m
  - Cont. to UA1 magnet
  - nd280m offline software
- Funding situation: ~60% secured, funding for the Barrel and P0D ECALs deferred for decision this year budget problems in the UK make this potentially problematic.

- United States – Contributions:
  - Cont. to SK, including upgrades, rebuild, and new SK electronics
  - P0D (all)
  - Beamline SC corrector magnets, 2nd horn, monitor electronics and GPS
  - Cont. to SMRD (photosensors, cont. to scintillators, mechanical, slow control)
  - nd280m offline software
  - Funding situation: secured, helped by forward cash flow from institutions. (US budget contained large cut for HEP, however this was targeted on other programmes and we are hopeful that T2K will not be effected).

## J-PARC PAC Jan. '08 Overall funding situation...

- Mostly good. The only major uncertainty for committed items is the UK funding for the ECAL, which hopefully we should find out soon.
- However, as you know, there is no overall cash reserve or contingency for the project.
- This produced a potential problem for items which are not clearly any one group's responsibility, in particular, the installation of the magnet and the detector cooling system.

An additional major financial risk was the uncertainty in the costs of shipping and installing the magnet.

# T2K IFOP

- The T2K IFOP has now been convened to allow discussion of common issues with and amongst the funding bodies.
- First meeting held Nov. 16th by telecon.
- Representatives from Japan, Canada, US, UK, France, and Switzerland.
- Agreed to T2K collaboration proposal for common costs to completion.
- Next meeting will be face-to-face at Tokai on February 26<sup>th</sup>.
- Bids now available for magnet shipment and installation, both within allowed financial envelope.

### ND280 Offline Software Status

- Software suite complete with set of packages for simulation-reconstruction-analysis chain
- Modular reconstruction and analysis frameworks, with fully object-oriented design
- Based on C++, Geant4, and ROOT
- Software framework stable, but algorithms undergoing rapid development – algorithm performance shown here is a snapshot of the current state!
- "User Release" imminent, with consistent user interface and documentation and user support mechanism

Report for PAC January 2008

#### Software Status

## Simulation



A CC1 $\pi$  interaction in the P0D, with full-bunch background

- Interfaces with all widelyused neutrino interaction generators
- Custom detector response (Scintillator detectors and TPC) and electronics (Trip-t and AFTER) simulations
   <u>T2K ND280 Offline Software Group</u>

- Geant4-based simulation
- Simulates full-spill interactions, and additional planted interactions for signal studies



### Reconstruction

- P0D, TPC, FGD & ECAL have full "MC truth-free" reconstruction algorithms
- Many algorithms in 2nd and 3rd generation
- SMRD reconstruction being developed, dependent on inner subdetector progress
- Subdetector-level and crossdetector reconstruction assisted by an external event reconstruction toolkit (RecPack) and flexible reconstruction I/O classes

**T2K ND280 Offline Software Group** 



#### Report for PAC January 2008

## **Tracker CCQE Selection**

Vertex in FGD fiducial volume
 A single possible TPC track

A single negative TPC track
No π<sup>+</sup> decay in FGD at vertex

# Iterative reconstruction

between FGDs and TPCs with RecPack

### Undergoing tuning:

- Barrel & Downstream ECAL  $\pi^0$  reconstruction for CC1 $\pi^0$  rejection
- TPC dE/dx PID
- Full-spill background rejection



#### Preliminary Reconstruction Software Demonstration

#### **T2K ND280 Offline Software Group**

#### Report for PAC January 2008

### **Tracker CCQE Selection**

#### Preliminary Reconstruction Software Demonstration



## PØD $\pi^0$ Selection

- Reconstructed vertex in fiducial volume
- No  $\mu$ -like tracks
- 2 or 3 candidate showers
- At least one shower
   > 10 cm from vertex
- No  $\mu$  decay candidates
- Event topology consistent with π<sup>0</sup>
- **Ongoing Work**
- Charged track and shower selection
- Shower vertex reconstruction
- 3D shower matching

T2K ND280 Offline Software Group

#### Preliminary Reconstruction Software Demonstration



## PØD $\pi^0$ Selection

- Expected performance based on generator information
- Efficiency: 33 % (this study: 19%)
- Purity: 50 % (this study: 34%)

#### Reconstructed $\pi^0$ Energy



T2K ND280 Offline Software Group



Ongoing work to meet expected efficiencies

Report for PAC January 2008

Preliminary Reconstruction Software Demonstration

### Summary

- T2K is making excellent progress.
- We still believe we can meet our ambitious schedule, and should have all major components operational (with the exception of the Barrel ECAL) by the end of 2009.
- On April 1<sup>st</sup>, 2009 the INGRID will be ready to take neutrino data for commissioning the beamline.
- A significant physics run in early 2010 should therefore allow us to achieve the world's best sensitivity to  $\theta_{13}$  and begin the era when T2K leads to world's neutrino oscillation experiments.
- In order to actually analyze this data we will need significant computing resources (~400 cores, ~50 TB) onsite, which should be provided by the host. This request has been made to KEK, and is critical Dave Wark to obtaining early physics results.